



INSPECTION REPORT

TIC 3181-13

OBJECT Power cable system consisting of 1-core power cable, 2 terminations, and 1 joint

64/110 (123) kV – 1x2000 mm² – Cu – XLPE

CLIENT OMACS LLC,
Moscow, Russia

MANUFACTURERS

Cable	Estralin HVC LLC, Moscow, Russia
Accessory 1	ARKASIL SK LLC, Moscow, Russia
Accessory 2	ARKASIL SK LLC, Moscow, Russia
Accessories	See section 1.1.3 Characteristics of the accessories

REFERENCE 72130463

INSPECTED BY KEMA Nederland B.V.,
Arnhem, The Netherlands

TEST LOCATION OMACS LLC,
Moscow, Russia

DATE(S) OF TESTS 1 March untill 30 September 2013

TEST SPECIFICATION The tests have been carried out based on IEC 60840 (2011).

SUMMARY AND CONCLUSION The cable system passed the tests.

This report applies only to the object tested. The responsibility for conformity of any object having the same type references as that tested rests with the manufacturer.

This report consists of 61 pages in total.

Copyright: Only integral reproduction of this report is permitted without written permission from KEMA. Electronic copies in e.g. PDF-format or scanned version of this report may be available and have the status "for information only". The sealed and bound version of the report is the only valid version.

KEMA Nederland B.V.

S.A.M. Verhoeven
Director Testing, Inspections &
Certification The Netherlands

Arnhem, 19 December 2013